Pearson's Candy Company Energy Conservation

Lydia DeBuhr MnTAP Advisor: Jane Paulson Company Supervisor: Alex Allen

UNIVERSITY OF MINNESOTA Driven to Discover^{ss}




Pearson's Candy Company

- •St. Paul, Minnesota
- •Founded 1909
- •Current building since 1959
- •Salted Nut Roll, Bit-O-Honey, Nut Goodie, Mint Patties, and BUN candies.





Process Overview



•Kitchen:

•Candy cooked and mixed

•Starch:

Centers formed

Production

•Centers and coatings combined •Finished candy packaged

•Warehouse:

•Packaged candy shipped out

Project Overview

Lighting

•LED

•Occupancy sensors •Weekend shutdown

•HVAC

•RFP

•System upgrade/redesign

Compressed Air

•Find, tag and record leaks

Recheck fixed leaks

Install valves at exhaust points

Insulation

•Thermal insulating paint

•Air Scrubber

•Design wastewater reuse



Approach




Mapping Te

Testing

Analysis

Consulting Data Collection





Motivation



- Increase efficiency
- Modernize equipment
- Xcel Energy assessment
- •Energy savings with rebates
 - •Rebates offered on energy conservation projects
 - •Additional Turn Key rebates on projects completed within a year
 - •St. Paul Port Authority Trillion BTU program

Primary Recommendation: Lighting

Equipment Change

- Install occupancy sensor switches
- •Re-lamp full plant with LEDs
- •Upgrade fixtures and lamps in office



Benefits

•LEDs

- •180,000 kWh saved annually
- •\$16,000 saved annually
- •4 month payback

•Occupancy sensors (before LED upgrade)

- •13,000 kWh saved annually
- •\$1,400 saved annually
- •8 month payback



Primary Recommendation: Lighting












Procedure Change

- •Turn off warehouse lights nightly
- •Turn off kitchen and main plant lights Friday nights
- •Annual Savings:

•86,000 kWh

•\$9,000



Mh

Solutions

reduction	Total cost	savings	Payback period	Status
86,000 kWh	-none-	\$9,000	Immediate	Implemented 8/7/20
180,000 kWh	\$5,000	\$16,000	4 months	Recommended
13,000 kWh	\$900	\$1,400	8 months	Recommended
220,000 kWh	-none-	\$24,000	Immediate	Implementing
120,000 kWh	Pending	\$13,000	Pending	Recommended
47,000 gal. water	\$500*	\$1,500	4 months	Recommended
N/A	N/A	N/A	N/A	Not Recommended
4	180,000 kWh 13,000 kWh 220,000 kWh 120,000 kWh	180,000 kWh \$5,000 13,000 kWh \$900 220,000 kWh -none- 120,000 kWh Pending 47,000 gal. water \$500*	180,000 kWh \$5,000 \$16,000 13,000 kWh \$900 \$1,400 220,000 kWh -none- \$24,000 120,000 kWh Pending \$13,000 47,000 gal. water \$500* \$1,500 N/A N/A N/A	180,000 kWh \$5,000 \$16,000 4 months 13,000 kWh \$900 \$1,400 8 months 220,000 kWh -none- \$24,000 Immediate 120,000 kWh Pending \$13,000 Pending 47,000 gal. water \$500* \$1,500 4 months




Personal Experience




Cool side, unpainted

Insulating Paint

- •Paint claimed to improve the insulating properties of a wall
- •No significant difference was detected



Hot side, thermal



Cool side, painted



Cool side



Hot side



UNIVERSITY OF MINNESOTA